



REPORT NO:
237 Valley Closure Assessment Report –
2024



MineLock
Environmental Engineers

Environmental Impact Management
Services (EIMS)

Closure and Financial Provision
Assessment of Valley TSF at Harmony
Gold mine, using the DMR Guidelines
as at January 2024

Table of Contents

1. INTRODUCTION	2
1.1 Background	2
2. MINE OVERVIEW	3
3. CLOSURE COST ASSESSMENT	4
3.1 Input parameters for quantum provision	4
3.2 Primary Risk Class for type of minerals mined.....	4
3.3 Risk Class	4
3.4 Area Sensitivity.....	4
3.5 Closure components	5
3.6 Unit rates for closure components	7
3.7 Weighting Factor 1 and 2	7
3.8 Escalation.....	8
3.9 Closure methods and assumptions.....	8
3.9.1 Components 2 (B): Steel and reinforced concrete structures and housing, facilities and services	8
3.9.2 Component 10: General surface rehabilitation	8
3.9.3 Component 12: Fencing.....	9
3.9.4 Costs	10
4. CONCLUSION	12
5. RECOMMENDATIONS	12
6. REFERENCES	12

1. INTRODUCTION

1.1 Background

MineLock Environmental Engineers (MineLock) was commissioned by Environmental Impact Management Services (EIMS) to develop an premature DME closure quantum as part of the Basic Assessment, for the newly designed Valley tailings storage facility (TSF) at the Harmony Gold Mining Company Limited (Harmony), areas between the Free State North 1 (FSN) and Free State North 2 (FSN) TSFs.

A new deposition site will be required for Harmony One Plant to replace the FSS2 and St. Helena 4 TSFs. Several alternative sites were identified and assessed by Harmony as possible suitable deposition sites for the tailings from Harmony One Plant after June 2024 but was found not feasible.

Following a review of other possibilities for One Plant's future tailings deposition by Harmony, an option to utilise the space between the Free State North 1 (FSN) and Free State North 2 (FSN) TSFs and portion of the footprint of the FSN4 TSF as shown in the Google Earth image in Figure 1 below has been identified as possible deposition site.



Figure 1: Google Earth image of the position of the proposed Valley TSF

For premature closure, only relevant activities within a year from the first day of disturbance of the Valley TSF was considered. According to the schedule provided by EIMS (see Appendix A), the construction of the Valley TSF is planned to take 276 working days, starting on 28 April 2025 and ending on 18 May 2026, thus the earthworks, bottom liner system and supporting infrastructure are to be demolished during year one of the premature closure.

The following items were considered for the Year 1 premature closure quantum of the Valley TSF:

- Removal of bottom barrier system;
- Removal of underdrainage system;
- Demolition of all embankments;
- Rehabilitation of Valley area; and
- Decommissioning of Return water dam and supporting infrastructure.

The embankments and bottom liner system designs as designed and provided by Geotheta, Appendix A, was incorporated into the premature closure quantum.

No allowance was made for Post closure monitoring and aftercare as part of the premature closure quantum as no tailings material has been deposited during this first year period. Allowance for Year 2, which will include commissioning and deposition of tailings material, should form part of Harmony Gold's upcoming annual update.

2. MINE OVERVIEW

Harmony is a gold mine located approximately 8km north-west of Welkom in the Free State.

Table 1 presents the infrastructure and features associated with the Valley TSF.

Table 1: Activities as per DMR Guidelines

Component	Description	Applicable
1	Dismantling of processing plant and related structures (incl. overland conveyors and Power lines)	N/A
2 (A)	Demolition of steel buildings and structures	N/A
2 (B)	Demolition of reinforced concrete buildings and structures	Silt Trap Culvert Solution outfall trench Spillway Decant manholes and pump chamber
3	Rehabilitation of access roads	N/A
4 (A)	Demolition and rehabilitation of electrified railway lines	N/A
4 (B)	Demolition and rehabilitation of non-electrified railway lines	N/A
5	Demolition of housing and/or administration facilities	N/A
6	Opencast rehabilitation including final voids and ramps	N/A
7	Sealing of shafts, adits and inclines	N/A
8 (A)	Rehabilitation of overburden and spoils	N/A
8 (B)	Rehabilitation of processing waste deposits and evaporation ponds (basic, salt producing waste)	N/A
8 (C)	Rehabilitation of processing waste deposits and evaporation ponds (acidic, metal-rich waste)	N/A
9	Rehabilitation of subsided areas	N/A
10	General surface rehabilitation	Valley Tailings Storage Facility assumed to be empty at this stage and no deposition has taken place Topsoil footprint 1 Topsoil footprint 2

Component	Description	Applicable
		RWD liner removal assumed allowed for in general surface rehabilitation rate
11	River diversions	N/A
12	Fencing	RWD Perimeter fence
13	Water management	N/A
14	2 to 3 years of maintenance and aftercare	N/A

3. CLOSURE COST ASSESSMENT

This section presents the basis of the calculation of the quantum for financial provisions for closure. The assessment and calculations are based on the 2005 DMR 'Guideline Document for the Evaluation of the Quantum of Closure-Related Financial Provision' provided by a Mine (Department of Mineral Resources, 2005).

3.1 Input parameters for quantum provision

No	Input data
1	Risk ranking for mine type and mineral by-product
2	Environmental sensitivity of the mining area
3	Level of information available
4	Type of mining operation
5	Geographical location of the mine
6	Closure components & Areas of disturbance (Components Map)

3.2 Primary Risk Class for type of minerals mined

Mineral	Ore	Size: Larger if > than (tpm)	Primary risk class			
			Large Mine		Small Mine	
			Mine and mine waste	Mine, mine waste, plant and plant waste	Mine and mine waste	Mine, mine waste, plant and plant waste
Gold		10 000	B	A	B	A

3.3 Risk Class

Determine risk class	
Class A	a high probability of the occurrence of the impact with a severe consequence,
Class B	a moderate probability of occurrence of the impact with a manageable consequence,
Class C	a low probability of occurrence of the impact with a negligible consequence.

3.4 Area Sensitivity

Area sensitivity			
Sensitivity	Sensitivity criteria		
	Biophysical	Social	Economic
Low	<ul style="list-style-type: none"> Largely disturbed from natural state. Limited natural fauna and flora remains. Exotic plant species evident. Unplanned development. 	<ul style="list-style-type: none"> The local communities are not within sighting distance of the mining operation. Lightly inhabited area (rural). 	<ul style="list-style-type: none"> The area is insensitive to development. The area is not a major source of income to the local communities.

	<ul style="list-style-type: none"> • Water resources disturbed and impaired. 		
Medium	<ul style="list-style-type: none"> • Mix of natural and exotic fauna and flora. • Development is a mix of disturbed and undisturbed areas, within an overall planned framework. • Water resources are well controlled. 	<ul style="list-style-type: none"> • The local communities are in the proximity of the mining operation (within sighting distance). • Peri-urban area with density aligned with a development framework. • Area developed with an established 	<ul style="list-style-type: none"> • The area has a balanced economic development where a degree of income for the local communities is derived from the area. • The economic activity could be influenced by indiscriminate development.
High	<ul style="list-style-type: none"> • Largely in natural state. • Vibrant fauna and flora, with species diversity and abundance matching the nature of the area. • Well planned development. • Area forms part of an overall ecological regime of conservation value. • Water resources emulate their original state. 	<ul style="list-style-type: none"> • The local communities are in close proximity of the mining operation (on the boundary of the mine). • Densely inhabited area (urban/dense settlements). • Developed and well-established communities. 	<ul style="list-style-type: none"> • The local communities derive the bulk of their income directly from the area. • The area is sensitive to development that could compromise the existing economic activity.

3.5 Closure components

Component No.	Main description	Applicable closure components for mine type		
		Open-cast	Under ground	Combination
1	Dismantling of processing plant and related structures (including overland conveyors and power lines)	No	No	No
2(A)	Demolition of steel buildings and structures	No	No	No
2(B)	Demolition of reinforced concrete buildings and structures	No	No	Yes
3	Rehabilitation of access roads	No	No	No
4(A)	Demolition and rehabilitation of electrified railway lines	No	No	No
4(B)	Demolition and rehabilitation of non-electrified	No	No	No

Component No.	Main description	Applicable closure components for mine type		
		Open-cast	Under ground	Combination
	railway lines			
5	Demolition of housing and facilities	No	No	No
6	Opencast rehabilitation including final voids and ramps	No	No	No
7	Sealing of shafts, adits and inclines	No	No	No
8(A)	Rehabilitation of overburden and spoils	No	No	No
8(B)	Rehabilitation of processing waste deposits and evaporation ponds (basic, salt-producing waste)	No	No	No
8(C)	Rehabilitation of processing waste deposits and evaporation ponds (acidic, metal-rich waste)	No	No	No
9	Rehabilitation of subsided areas	No	No	No
10	General surface rehabilitation, including grassing of all denuded areas	No	No	Yes
11	River diversions	No	No	No
12	Fencing	No	No	Yes
13	Water management (Separating clean and dirty water, managing polluted water and managing the impact on groundwater, including treatment, when required)	No	No	No
14	2 to 3 years of maintenance and aftercare	No	No	No

3.6 Unit rates for closure components

The components in the DMR guideline that has multiplication factors different than 1 are listed below. It is, however, not necessarily applicable to the costing of this site.

Component 6 - Opencast Rehabilitation:

COMPONENT 6		OPENCAST REHABILITATION		
		UNIT		MASTER RATE
		<i>ha</i>		R 213 206.21
		Multiplication factor		
Risk Class (A, B or C)	A	0.04	0.52	1.00
	B	0.04	0.52	1.00
	C	0.04	0.52	1.00
		Low	Medium	High
		Environmental Sensitivity		

Component 8 (c) - Processing water deposits & Evaporation ponds:

COMPONENT 8 (C)		PROCESSING WATER DEPOSITS & EVAPORATION PONDS		
		UNIT		MASTER RATE
		<i>ha</i>		R 529 598.05
		Multiplication factor		
Risk Class (A, B or C)	A	0.59	0.80	1.00
	B	0.55	0.76	0.90
	C	0.51	0.66	0.81
		Low	Medium	High
		Environmental Sensitivity		

Component 13 – Water Management:

COMPONENT 13		WATER MANAGEMENT		
		UNIT		MASTER RATE
		<i>ha</i>		R 44 096.42
		Multiplication factor		
Risk Class (A, B or C)	A	0.60	0.67	1.00
	B	0.41	0.60	0.67
	C	0.17	0.25	0.33
		Low	Medium	High
		Environmental Sensitivity		

3.7 Weighting Factor 1 and 2

Weighting factor 1 is applied to all closure components:

Nature of the Terrain/Accessibility	Flat	Undulating	Rugged
Weighting Factor 1	1.00	1.10	1.20

Weighting factor 2 is applied to preliminary and general item only:

Proximity to urban area where goods and services are supplied	Urban	Peri-urban	Remote
Weighting Factor 2	1.00	1.05	1.10

3.8 Escalation

In South Africa, the Consumer Price Index or CPI measures changes in the prices paid by consumers for a basket of goods and services and is published Stats SA (Consumer Price Index, Statistical Release P0141).

The master rates were updated (escalated) by multiplying the master rate of the previous year with the new (average) CPI value. The average CPI was published end of January 2024.

Table 2: Consumer price indices headline year-on-year rates

Year	Jan	Feb	March	Apr	May	Jun	Jul	Aug	Sept	Oct	Nov	Dec	Average
2023	6.9	7	7.1	6.8	6.3	5.4	4.7	4.8	5.4	5.9	5.5	5.1	5.91
2024	5.3	-	-	-	-	-	-	-	-	-	-	-	5.30

3.9 Closure methods and assumptions

The DMR Guideline presents generally accepted closure methods, based on experience in the field, which have been used as the basis for determining the Master Rates for the various closure components in the “rules-based” approach. Where relevant, specific reference is made to the site conditions and requirements applicable to the closure of the Valley TSF. In addition, the relevant mine structures and components requiring closure are listed.

3.9.1 Components 2 (B): Steel and reinforced concrete structures and housing, facilities and services

According to the DMR Guideline, the generally accepted closure methods applicable to this component include:

- All structures should be demolished to 1m below ground level.
- The rubble is to be buried adjacent to the sites, provided this adheres to the National Waste Management Strategy.
- Silos should be imploded and buried.
- The areas should be shaped, top soiled with 300mm of topsoil and vegetated or as stated in the relevant EMP document.
- Monitoring and maintenance are costed in the relevant areas.
- The concrete hardstand is the area between buildings such as workshops, offices, etc.

3.9.2 Component 10: General surface rehabilitation

Final surface rehabilitation of areas disturbed by mining and related activities should be aligned to the selected final land use. The generally accepted closure methods applicable to general surface rehabilitation includes:

- Surface topography that emulates the surrounding areas and aligned to the general landscape character. Steep slopes more than 6 percent should also be avoided if possible.
- Landscaping that would facilitate surface runoff and result in free draining areas. If possible, the drainage lines should be reinstated.

- An area without unnecessary remnants of structures and surface infrastructure to give the rehabilitated area a “neat” appearance. Special attention must be given to shape and/or removal of heaps of excess material being the legacy of prolonged mining and related activity.
- An area suitable for revegetation.

The unit cost for general rehabilitation allows for shaping and landscaping of disturbed areas. The Master Rate for the shaping of material to a depth/thickness of about 500mm. An extra over allowance in the unit cost of 50% has been made to cover the removal and/or destruction of surface infrastructure remnants and/or other undesirable objects such as trees, foundations, concrete slabs, etc.

In this study area it is assumed to include the removal of the liner systems for TSF and RWD.

3.9.3 Component 12: Fencing

This item includes the removal of all fencing structures. The fencing included for the RCM project includes all fences on the mine.

3.9.4 Costs

The quantum for financial provisions for un-scheduled closure was estimated using the rule-based approach defined in the DMR Guideline. Refer to Table 3 for a summarised breakdown of the closure cost assessment estimate as of January 2024.

Table 3: Summary of the unscheduled closure cost for RCM

CALCULATION OF THE QUANTUM							
MINE: HARMONY GOLD MINING COMPANY LIMITED				LOCATION: FREE STATE			
EVALUATORS: MINELOCK ENVIRONMENTAL ENGINEERS (PTY) LTD				DATE: 2024/03/20			
NO	DESCRIPTION	UNIT	A QUANTITY	B MASTER RATE DEC 2023	C MULTIPLICATI ON FACTOR	D WEIGHTING FACTOR	AMOUNT RAND JAN 2024
1	Dismantling of processing plant and related structures (Including overland conveyors and power lines)	m ³	-	R 19.45	1.00	1.00	R 0.00
2(A)	Demolition of steel buildings and structures	m ²	-	R 270.95	1.00	1.00	R 0.00
2(b)	Demolition of reinforced concrete buildings and structures	m ²	10 025.06	R 399.29	1.00	1.00	R 4 002 922.13
3	Rehabilitation of access roads Including all haul roads	m ²	-	R 48.49	1.00	1.00	R 0.00
4(A)	Demolition and rehabilitation of electrified railway lines	m	-	R 470.60	1.00	1.00	R 0.00
4(B)	Demolition and rehabilitation of non-electrified railway lines	m ²	-	R 256.69	1.00	1.00	R 0.00
5	Demolition of housing and/or administration facilities	m ²	-	R 541.91	1.00	1.00	R 0.00
6	Opencast rehabilitation including final voids and ramps	ha	-	R 275 798.43	0.52	1.00	R 0.00
7	Sealing of shafts, adits and inclines	m ³	-	R 145.46	1.00	1.00	R 0.00
8(A)	Rehabilitation of overburden and spoils	ha	-	R 189 379.68	1.00	1.00	R 0.00

CALCULATION OF THE QUANTUM							
MINE: HARMONY GOLD MINING COMPANY LIMITED				LOCATION: FREE STATE			
EVALUATORS: MINELOCK ENVIRONMENTAL ENGINEERS (PTY) LTD				DATE: 2024/03/19			
NO	DESCRIPTION	UNIT	A QUANTITY	B MASTER RATE DEC 2023	C MULTIPLICATION FACTOR	D WEIGHTING FACTOR	AMOUNT RAND JAN 2024
8(B)	Rehabilitation of processing waste deposits and evaporation ponds (basic, salt-producing waste)	ha	-	R 235 868.97	1.00	1.00	R 0.00
8(C)	Rehabilitation of processing waste deposits and evaporation ponds (acidic, metal-rich waste)	ha	-	R 685 075.31	0.80	1.00	R 0.00
9	Rehabilitation of subsided areas	ha	-	R 158 576.97	1.00	1.00	R 0.00
10	General surface rehabilitation	ha	136.05	R 150 020.65	1.00	1.00	R 20 410 999.66
11	River diversions	ha	-	R 150 020.65	1.00	1.00	R 0.00
12	Fencing	m	1 500.00	R 171.13	1.00	1.00	R 256 694.56
13	Water management	ha	-	R 57 042.07	0.67	1.00	R 0.00
14	Maintenance and aftercare	ha	-	R 19 964.73	1.00	1.00	R 0.00
15(A)	Specialist study	Sum	-	R 0.00	1.00	1.00	R 0.00
15(B)	Specialist study	Sum	-	R 0.00	1.00	1.00	R 0.00
Sub Total 1							R 24 670 616.35
Weighting factor 2 (1)							R 24 670 616.35
1	Preliminary and general				12 % of Sub Total 1		
Sub Total 2							R 2 960 473.96
7	Contingencies				10 % of Sub Total 1		
Grand Total 3							R 27 631 090.31
Grand Total 3							R 30 098 151.94

4. CONCLUSION

The financial provision for premature rehabilitation and closure for Valley TSF for Harmony is documented in this Report. All information was provided by EIMS and Harmony. No site visits were conducted and in those cases where information was not available, estimates / assumptions were made based on experience.

The Master Rates was escalated with an average CPI published until end January 2024.

Notwithstanding the above, the premature closure quantum documented in this Report reflects the costs for premature closure costs provision in January 2024 aligned with the Harmony current approved EMPR.

5. RECOMMENDATIONS

Aspects that that require further attention have been identified. These aspects may improve the accuracy of futures closure cost estimates.

- To ensure that the financial provision is up-to-date and in accordance to the NEMA requirements, annual revision of closure costing is recommended. This will also assist in accommodating changes in the closure costing due to any facilities that was constructed or demolished as well as any changes in the closure approach;

6. REFERENCES

Department of Mineral Resources, 2005. *Guideline Document for The Evaluatuon of The Quantum of Closure-Related Financial Provision Provided by a Mine*, s.l.: s.n.

Department: Statistics South Africa, 2024. Statistical Release P0141. *Consumer Price Index January 2024*, January.

Environmental Impact Management Services, 2023. *Environmental Management Programme. Proposed Harmony Valley Tailings Storage Facility Project*, s.l.: s.n.





Douglas Richards
Director



Is-Mari Kretschmer
Civil Engineer

APPENDIX A

Geotheta drawings and schedule




ISSUED FOR INFORMATION

REVISIONS		REFERENCE DRAWINGS		REFERENCE DRAWINGS		
REV	DATE	DESCRIPTION	DRG.No.	DRAWING TITLE	DRG.No.	DRAWING TITLE
A	2023-08-25	ISSUED FOR INFORMATION	502	PRE-DEPOSITION WORKS GENERAL ARRANGEMENT		
			503	FINAL HEIGHT GENERAL ARRANGEMENT		

<p>GEOTHETA CONSULTING ENGINEERS AND SCIENTISTS</p> <p>Ground Floor, Twickenham Building, The Campus, Cnr Searns & Main, Bryanston, 2021 Republic of South Africa Phone : +27 11 575 3002 E-mail : hello@geotheta.com</p>					
APPROVED BY					
NAME	QUALIFICATION & REG. No.	SIGNATURE	DATE	CO-ORD SYSTEM	SCALE
IAN HAMMOND	PR.ENG 20110169		2023-08	WGS 84 LO27	A1 1:15000 A3 1:30000

<p>DRWN 2023-08-25</p> <p>DATE</p> <p>CHECKED S.M.</p> <p>DATE</p> <p>DESIGNED S.M./I.H.</p> <p>DATE</p> <p>2023-08-18</p>	<p>CLIENT HARMONY</p> <p>TITLE HARMONY - VALLEY TSF (CYCLONED) OVERALL SITE LAYOUT</p> <p>DRG No. 2210513-501</p> <p>REV. A</p>
--	---

COPYRIGHT IN THIS DRAWING VESTS IN GEOTHETA, AND EXTENDS TO THE TAKING OF COPIES THEREOF IN WHOLE OR PART WITHOUT THE PRIOR CONSENT OF THE OWNER OF SUCH COPYRIGHT



LEGEND:

- TOPOGRAPHICAL CONTOURS - DATED 2023-02-01 (0.5m INTERVALS)
- AREA TO BE LINED
- EXISTING ACCESS ROADS

ISSUED FOR INFORMATION

REV	DATE	DESCRIPTION
A	2023-08-25	ISSUED FOR INFORMATION

DRG.No.	DRAWING TITLE
503	FINAL HEIGHT GENERAL ARRANGEMENT
504	EARTHWORKS SECTIONS
505	EARTHWORKS SECTIONS & DETAILS
506	DRAINAGE SECTIONS & DETAILS
507	DRAINAGE COLLECTOR PIPES SECTIONS & DETAILS
508	SOLUTION TRENCH SECTIONS & DETAILS
509	PENSTOCK INTAKE SECTIONS & DETAILS
510	PENSTOCK CATWALK TYPICAL DETAILS

DRG.No.	DRAWING TITLE
511	SOLUTION OUTFALL TRENCH PLAN, SECTIONS & DTLS
601	RWD SILT TRAP PLAN, SECTIONS & DETAILS
604	RETURN WATER DAM GENERAL ARRANGEMENT

NAME	QUALIFICATION & REG. No.	SIGNATURE	DATE
IAN HAMMOND	PR.ENG 20110169		2023-08

GEOTHETA CONSULTING ENGINEERS AND SCIENTISTS

Ground Floor, Twickenham Building, The Campus, Cnr Skane & Main, Bryanston, 2021 Republic of South Africa
Phone : +27 11 575 3002
E-mail : hello@geotheta.com



APPROVED BY

NAME	QUALIFICATION & REG. No.	SIGNATURE	DATE
IAN HAMMOND	PR.ENG 20110169		2023-08

DATE	SCALE
2023-08-25	A1 1:5000
2023-08-31	A3 1:10000

CLIENT	TITLE	DRG No.	REV.
HARMONY	HARMONY - VALLEY TSF (CYCLONED) PRE-DEPOSITION WORKS GENERAL ARRANGEMENT	2210513-502	A

COPYRIGHT IN THIS DRAWING VESTS IN GEOTHETA, AND EXTENDS TO THE TAKING OF COPIES THEREOF IN WHOLE OR PART WITHOUT THE PRIOR CONSENT OF THE OWNER OF SUCH COPYRIGHT



LEGEND:	
	TOPOGRAPHICAL CONTOURS - DATED 2023-02-01 (0.5m INTERVALS)
	EXISTING ACCESS ROADS

ISSUED FOR INFORMATION

REV	DATE	DESCRIPTION
A	2023-08-25	ISSUED FOR INFORMATION

DRG.No.	DRAWING TITLE
503	FINAL HEIGHT GENERAL ARRANGEMENT
504	EARTHWORKS SECTIONS
505	EARTHWORKS SECTIONS & DETAILS
506	DRAINAGE SECTIONS & DETAILS
507	DRAINAGE COLLECTOR PIPES SECTIONS & DETAILS
508	SOLUTION TRENCH SECTIONS & DETAILS
509	PENSTOCK INTAKE SECTIONS & DETAILS
510	PENSTOCK CATWALK TYPICAL DETAILS

DRG.No.	DRAWING TITLE
511	SOLUTION OUTFALL TRENCH PLAN, SECTIONS & DTLS
601	RWD SILT TRAP PLAN, SECTIONS & DETAILS
604	RETURN WATER DAM GENERAL ARRANGEMENT

NAME	QUALIFICATION & REG. No.	SIGNATURE	DATE
IAN HAMMOND	PRE.ENG 20110169		2023-08

GEOTHETA CONSULTING ENGINEERS AND SCIENTISTS
 Ground Floor, Twickenham Building, The Campus, Cnr Skene & Main, Bryanston, 2021
 Republic of South Africa
 Phone : +27 11 575 3002
 E-mail : hello@geotheta.com


APPROVED BY: _____

DATE: 2023-08-18


DATE	SCALE
2023-08-25	A1 1:5000
S.M.	A3 1:10000
2023-08-31	
S.M./I.H.	
2023-08-18	

CLIENT	TITLE	DRG No.	REV.
HARMONY	HARMONY - VALLEY TSF (CYCLONED) FINAL HEIGHT GENERAL ARRANGEMENT	2210513-503	A

COPYRIGHT IN THIS DRAWING VESTS IN GEOTHETA, AND EXTENDS TO THE TAKING OF COPIES THEREOF IN WHOLE OR PART WITHOUT THE PRIOR CONSENT OF THE OWNER OF SUCH COPYRIGHT



SECTION A
1:200



SECTION B
1:300

ISSUED FOR INFORMATION





REVISIONS		REFERENCE DRAWINGS		REFERENCE DRAWINGS		
REV	DATE	DESCRIPTION	DRG.No.	DRAWING TITLE	DRG.No.	DRAWING TITLE
A	2023-08-25	ISSUED FOR INFORMATION	502	PRE-DEPOSITION WORKS GENERAL ARRANGEMENT		
			503	FINAL HEIGHT GENERAL ARRANGEMENT		
			504	EARTHWORKS SECTIONS		
			505	EARTHWORKS SECTIONS & DETAILS		
			506	DRAINAGE SECTIONS & DETAILS		
			507	DRAINAGE COLLECTOR PIPES SECTIONS & DETAILS		
			508	SOLUTION TRENCH SECTIONS & DETAILS		

GEOTHETA CONSULTING ENGINEERS AND SCIENTISTS
 Ground Floor, Twickenham Building, The Campus,
 Cnr Skane & Main, Bryanston, 2021
 Republic of South Africa
 Phone : +27 11 575 3002
 E-mail : hello@geotheta.com

APPROVED BY				CO-ORD SYSTEM		SCALE	
NAME	QUALIFICATION & REG. No.	SIGNATURE	DATE				
IAN HAMMOND	PR.ENG 20110169		2023-08			A1 AS SHOWN	A3 AS SHOWN X2



CLIENT		TITLE	
HARMONY		HARMONY - VALLEY TSF (CYCLONED) EARTHWORKS SECTIONS	
DRG No.	2210513-504	REV.	A

COPYRIGHT IN THIS DRAWING VESTS IN GEOTHETA, AND EXTENDS TO THE TAKING OF COPIES THEREOF IN WHOLE OR PART WITHOUT THE PRIOR CONSENT OF THE OWNER OF SUCH COPYRIGHT



DETAIL '1' - SECTION SHOWING LINER ANCHOR TRENCH
SCALE 1:25

TYPICAL SECTION - ACCESS ROAD
SCALE 1:50



DETAIL '2' - TYPICAL SECTION BARRIER SYSTEM (CENTRAL BASIN AREA)
SCALE 1:25

DETAIL '3' - TYPICAL SECTION BARRIER SYSTEM (BASIN AREA BETWEEN OUTER EMBANKMENTS)
SCALE 1:25


ISSUED FOR INFORMATION

REVISIONS		REFERENCE DRAWINGS		REFERENCE DRAWINGS		GEOETHETA CONSULTING ENGINEERS AND SCIENTISTS		DRAWN		CLIENT		
REV	DATE	DESCRIPTION	DRG.No.	DRAWING TITLE	DRG.No.	DRAWING TITLE	NAME	QUALIFICATION & REG. No.	SIGNATURE	DATE	DATE	HARMONY
A	2023-08-25	ISSUED FOR INFORMATION	502	PRE-DEPOSITION WORKS GENERAL ARRANGEMENT	.	.	IAN HAMMOND	PR.ENG	[Signature]	2023-08	2023-08-25	HARMONY
			503	FINAL HEIGHT GENERAL ARRANGEMENT							2023-08-31	TITLE
			504	EARTHWORKS SECTIONS							2023-08-18	HARMONY - VALLEY TSF (CYCLONED)
												EARTHWORKS
												SECTIONS & DETAILS
												DRG No.
												2210513-505
												REV.
												A


COPYRIGHT IN THIS DRAWING VESTS IN GEOETHETA, AND EXTENDS TO THE TAKING OF COPIES THEREOF IN WHOLE OR PART WITHOUT THE PRIOR CONSENT OF THE OWNER OF SUCH COPYRIGHT

NOTES:


- RIP & RECOMPACT BASE OF TRENCHES 150mm DEEP TO 95% PROCTOR DENSITY @ 0% TO +2% OF O.M.C.
- HDPE PIPE BOOT TO BLANKET DRAIN AT OUTLET PIPE. (SEE DETAIL '1').




TYPICAL SECTION - BLANKET DRAIN & LEAKAGE DETECTION DRAIN
SCALE 1:25




TYPICAL SECTION - DRAINAGE OUTLET PIPES
SCALE 1:25




TYPICAL SECTION - UNDERDRAINAGE SYSTEM ON PLATFORM (ABOVE LINER) (CENTRAL BASIN AREA)
SCALE 1:25




DETAIL '1' - TYPICAL SECTION HDPE PIPE BOOT
SCALE 1:15



TYPICAL SECTION - UNDERDRAINAGE SYSTEM (ABOVE LINER) (BASIN AREA BETWEEN OUTER EMBANKMENTS)
SCALE 1:25




DETAIL '2'
N.T.S.




TYPICAL SECTION - UNDERDRAINAGE SYSTEM (ABOVE LINER) (CENTRAL BASIN AREA)
SCALE 1:25

ISSUED FOR INFORMATION

REVISIONS		REFERENCE DRAWINGS		REFERENCE DRAWINGS		DRAWN		CLIENT								
REV	DATE	DESCRIPTION	DRG.No.	DRAWING TITLE	DRG.No.	DRAWING TITLE	DATE	SCALE	TITLE							
A	2023-08-25	ISSUED FOR INFORMATION	502	PRE-DEPOSITION WORKS GENERAL ARRANGEMENT			2023-08-25	S.M.	HARMONY - VALLEY TSF (CYCLONED) DRAINAGE SECTIONS & DETAILS							
			503	FINAL HEIGHT GENERAL ARRANGEMENT			2023-08-31	S.M.I.H.								
			505	EARTHWORKS SECTIONS & DETAILS			2023-08-18	SCALE								
			508	DRAINAGE COLLECTOR PIPES SECTIONS & DETAILS												
<p>APPROVED BY</p> <table border="1"> <thead> <tr> <th>NAME</th> <th>QUALIFICATION & REG. No.</th> <th>SIGNATURE</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td>IAN HAMMOND</td> <td>PRE.ENG 20110169</td> <td></td> <td>2023-08</td> </tr> </tbody> </table>							NAME	QUALIFICATION & REG. No.	SIGNATURE	DATE	IAN HAMMOND	PRE.ENG 20110169		2023-08	<p>5D</p> <p>CLIENT: HARMONY</p>	
NAME	QUALIFICATION & REG. No.	SIGNATURE	DATE													
IAN HAMMOND	PRE.ENG 20110169		2023-08													
<p>GROUND FLOOR, TWICKENHAM BUILDING, THE CAMPUS, Cnr Skane & Main, Bryanston, 2021 Republic of South Africa Phone : +27 11 575 3002 E-mail : hello@geotheta.com</p>							<p>DATE: 2023-08-25</p> <p>CHECKED: S.M.</p> <p>DESIGNED: S.M.I.H.</p> <p>DATE: 2023-08-18</p>		<p>DRG No. 2210513-506</p> <p>REV. A</p>							
<p>COPYRIGHT IN THIS DRAWING VESTS IN GEOTHETA, AND EXTENDS TO THE TAKING OF COPIES THEREOF IN WHOLE OR PART WITHOUT THE PRIOR CONSENT OF THE OWNER OF SUCH COPYRIGHT</p>							<p>SCALE: A1 AS SHOWN, A3 AS SHOWN X2</p>		<p>REV. A</p>							



**TYPICAL SECTION - DRAINAGE COLLECTOR PIPES
(CENTRAL BASIN AREA)**
SCALE 1:25




**PLAN - DRAINAGE COLLECTOR PIPES
(PRIOR TO STONE PLACEMENT)**
SCALE 1:25

ISSUED FOR INFORMATION


REVISIONS		REFERENCE DRAWINGS		REFERENCE DRAWINGS		DRAWN		CLIENT			
REV	DATE	DESCRIPTION	DRG.No.	DRAWING TITLE	DRG.No.	DRAWING TITLE	DATE	SCALE	NAME		
A	2023-08-25	ISSUED FOR INFORMATION	502	PRE-DEPOSITION WORKS GENERAL ARRANGEMENT	.	.	2023-08-25	AS SHOWN	IAN HAMMOND		
			503	FINAL HEIGHT GENERAL ARRANGEMENT				AS SHOWN X2			
			505	EARTHWORKS SECTIONS & DETAILS							
			506	DRAINAGE SECTIONS & DETAILS							
						GEOTHETA CONSULTING ENGINEERS AND SCIENTISTS Ground Floor, Twickenham Building, The Campus, Cnr Skane & Main, Bryanston, 2021 Republic of South Africa Phone : +27 11 575 3002 E-mail : hello@geotheta.com				HARMONY HARMONY - VALLEY TSF (CYCLONED) DRAINAGE COLLECTOR PIPES SECTIONS & DETAILS	
						APPROVED BY NAME: IAN HAMMOND, QUALIFICATION & REG. No.: PR.ENG 20110169, SIGNATURE: [Signature], DATE: 2023-08		DATE: 2023-08-18, CO-ORD SYSTEM: ., SCALE:		DRG No. 2210513-507, REV. A	
COPYRIGHT IN THIS DRAWING VESTS IN GEOTHETA, AND EXTENDS TO THE TAKING OF COPIES THEREOF IN WHOLE OR PART WITHOUT THE PRIOR CONSENT OF THE OWNER OF SUCH COPYRIGHT											

NOTES:


1. WELD MESH TO BE REF 617 CENTRALLY PLACED.
2. MINIMUM REINFORCING LAP LENGTH TO BE 600mm.
3. EARTH ADJACENT TO CONCRETE TO BE COMPACTED.
4. ALL CONCRETE TO HAVE A SMOOTH FINISH.
5. ALL CONCRETE CORNERS IN CONTACT WITH THE LINING TO BE CHAMFERED MIN. 25mm.
6. ALL CONSTRUCTION JOINTS TO BE AS PER DETAIL '1'. PANEL SIZES TO BE APPROVED BY THE ENGINEER. JOINTS TO BE WELL CLEANED & SCRABBLED TO EXPOSE FRESH AGGREGATE & THOROUGHLY WETTED BEFORE NEXT POUR.



TYPICAL SECTION - SOLUTION TRENCH
SCALE 1:25



TYPICAL SECTION - SOLUTION TRENCH ON PLATFORM
SCALE 1:25



**DETAIL '1' - SECTION
CONSTRUCTION JOINT**
N.T.S.

ISSUED FOR INFORMATION


REVISIONS		REFERENCE DRAWINGS		REFERENCE DRAWINGS		DRAWN		CLIENT	
REV	DATE	DESCRIPTION	DRG.No.	DRAWING TITLE	DRG.No.	DRAWING TITLE	DATE	SCALE	CLIENT
A	2023-08-25	ISSUED FOR INFORMATION	502	PRE-DEPOSITION WORKS GENERAL ARRANGEMENT			2023-08-25		HARMONY
			503	FINAL HEIGHT GENERAL ARRANGEMENT			2023-08-31		HARMONY - VALLEY TSF (CYCLONED) SOLUTION TRENCH SECTIONS & DETAILS
			505	EARTHWORKS SECTIONS & DETAILS			2023-08-18		
						APPROVED BY		CO-ORD SYSTEM	
						NAME	QUALIFICATION & REG. No.	SIGNATURE	DATE
						IAN HAMMOND	PR.ENG 20110169		2023-08
						SCALE		REV.	
						A1 AS SHOWN		DRG No. 2210513-508	
						A3 AS SHOWN X2		A	

GEOTHETA CONSULTING ENGINEERS AND SCIENTISTS
Ground Floor, Twickenham Building, The Campus,
Cnr Skane & Main, Bryanston, 2021
Republic of South Africa
Phone : +27 11 575 3002
E-mail : hello@geotheta.com



COPYRIGHT IN THIS DRAWING VESTS IN GEOTHETA, AND EXTENDS TO THE TAKING OF COPIES THEREOF IN WHOLE OR PART WITHOUT THE PRIOR CONSENT OF THE OWNER OF SUCH COPYRIGHT

NOTES:


- UNLESS OTHERWISE INDICATED, ALL PIPES & FITTINGS TO BE CLASS PN10 PE 100 HDPE PLAIN ENDED SECTIONS.
- UNLESS OTHERWISE INDICATED, ALL HDPE PIPES AND FITTINGS TO BE JOINED BY ELECTRO FUSION WELDING.
- ALL CONCRETE CORNERS IN CONTACT WITH THE LINING TO BE CHAMFERED MIN. 25mm.




PLAN - PENSTOCK INTAKE
SCALE 1:25




SECTION A - A
SCALE 1:25



SECTION B - B
SCALE 1:25



DETAIL '1' - TYPICAL SECTION LINER ATTACHMENT TO CONCRETE
SCALE 1:10




ISSUED FOR INFORMATION




REVISIONS		REFERENCE DRAWINGS		REFERENCE DRAWINGS		
REV	DATE	DESCRIPTION	DRG.No.	DRAWING TITLE	DRG.No.	DRAWING TITLE
A	2023-08-25	ISSUED FOR INFORMATION	502	PRE-DEPOSITION WORKS GENERAL ARRANGEMENT		
			503	FINAL HEIGHT GENERAL ARRANGEMENT		
			505	EARTHWORKS SECTIONS & DETAILS		

<p>GEOTHETA CONSULTING ENGINEERS AND SCIENTISTS</p> <p>Ground Floor, Twickenham Building, The Campus, Cnr Skane & Main, Bryanston, 2021 Republic of South Africa Phone : +27 11 575 3002 E-mail : hello@geotheta.com</p>				<p>DRAWN: 2023-08-25</p> <p>CHECKED: S.M.</p> <p>DATE: 2023-08-31</p> <p>DESIGNED: S.M.I.H.</p> <p>DATE: 2023-08-18</p>		<p>CLIENT: HARMONY</p> <p>TITLE: HARMONY - VALLEY TSF (CYCLONED) PENSTOCK INTAKE SECTIONS & DETAILS</p>	
<p>APPROVED BY:</p> <p>NAME: IAN HAMMOND, QUALIFICATION & REG. No.: PR.ENG 20110169, SIGNATURE: [Signature], DATE: 2023-08</p>				<p>CO-ORD SYSTEM: A1 AS SHOWN, SCALE: AS SHOWN X2</p>		<p>DRG No.: 2210513-509, REV. A</p>	


COPYRIGHT IN THIS DRAWING VESTS IN GEOTHETA, AND EXTENDS TO THE TAKING OF COPIES THEREOF IN WHOLE OR PART WITHOUT THE PRIOR CONSENT OF THE OWNER OF SUCH COPYRIGHT




PLAN - PLATFORM AT PENSTOCK INTAKE
SCALE 1:50




ELEVATION A - A PLATFORM AT PENSTOCK INTAKE
SCALE 1:50




SECTION B - B PLATFORM AT PENSTOCK INTAKE
SCALE 1:50



SECTION E - E CATWALK
SCALE 1:50



SECTION F - F CATWALK
SCALE 1:50



PLAN CATWALK
SCALE 1:50

ISSUED FOR INFORMATION

REVISIONS		REFERENCE DRAWINGS		REFERENCE DRAWINGS		
REV	DATE	DESCRIPTION	DRG.No.	DRAWING TITLE	DRG.No.	DRAWING TITLE
A	2023-08-25	ISSUED FOR INFORMATION	502	PRE-DEPOSITION WORKS GENERAL ARRANGEMENT		
			503	FINAL HEIGHT GENERAL ARRANGEMENT		
			505	EARTHWORKS SECTIONS & DETAILS		
			509	PENSTOCK INTAKE SECTIONS & DETAILS		

APPROVED BY			
NAME	QUALIFICATION & REG. No.	SIGNATURE	DATE
IAN HAMMOND	PRE.ENG 20110169		2023-08



DRAWN		DATE	
		2023-08-25	
CHECKED		DATE	
		2023-08-31	
DESIGNED		DATE	
		2023-08-18	

CO-ORD SYSTEM		SCALE	
A1	AS SHOWN		
A3	AS SHOWN X2		

CLIENT		TITLE	
HARMONY		HARMONY - VALLEY TSF (CYCLONED) PENSTOCK CATWALK TYPICAL DETAILS	
DRG No.	REV.	2210513-510	
	A		

COPYRIGHT IN THIS DRAWING VESTS IN GEOTHETA, AND EXTENDS TO THE TAKING OF COPIES THEREOF IN WHOLE OR PART WITHOUT THE PRIOR CONSENT OF THE OWNER OF SUCH COPYRIGHT


GEOTHETA CONSULTING ENGINEERS AND SCIENTISTS
Ground Floor, Twickenham Building, The Campus, Cnr Skane & Math, Bryanston, 2021 Republic of South Africa
Phone : +27 11 575 3002
E-mail : hello@geotheta.com




PLAN - SOLUTION OUTFALL TRENCH
SCALE 1:100

NOTES:


1. WELD MESH TO BE REF 617 CENTRALLY PLACED.
2. MINIMUM REINFORCING LAP LENGTH TO BE 600mm.
3. EARTH ADJACENT TO CONCRETE TO BE COMPACTED.
4. ALL CONCRETE TO HAVE A SMOOTH FINISH.
5. ALL CONCRETE CORNERS IN CONTACT WITH THE LINING TO BE CHAMFERED MIN. 25mm.
6. ALL CONSTRUCTION JOINTS TO BE AS PER DETAIL '1'. PANEL SIZES TO BE APPROVED BY THE ENGINEER. JOINTS TO BE WELL CLEANED & SCRABBLED TO EXPOSE FRESH AGGREGATE & THOROUGHLY WETTED BEFORE NEXT POUR.



DETAIL '1' - SECTION CONSTRUCTION JOINT
N.T.S.



SECTION A - A
SCALE 1:50



SECTION B - B
SCALE 1:50

ISSUED FOR INFORMATION

REVISIONS		REFERENCE DRAWINGS		REFERENCE DRAWINGS		
REV	DATE	DESCRIPTION	DRG.No.	DRAWING TITLE	DRG.No.	DRAWING TITLE
A	2023-08-25	ISSUED FOR INFORMATION	502	PRE-DEPOSITION WORKS GENERAL ARRANGEMENT	.	.
			508	SOLUTION TRENCH SECTIONS & DETAILS		
			601	SILT TRAP PLAN, SECTIONS & DETAILS		

GEOTHETA CONSULTING ENGINEERS AND SCIENTISTS Ground Floor, Twickenham Building, The Campus, Cnr Skane & Main, Bryanston, 2021 Republic of South Africa Phone : +27 11 575 3002 E-mail : hello@geotheta.com				DRAWN 2023-08-25	5D CLIENT HARMONY
				CHECKED S.M.	
APPROVED BY NAME: IAN HAMMOND, QUALIFICATION & REG. No.: PR.ENG 20110169, SIGNATURE: [Signature], DATE: 2023-08				DATE 2023-08-18	DRG No. 2210513-511
CO-ORD SYSTEM WGS 84 LO27				SCALE A1 AS SHOWN A3 AS SHOWN X2	

COPYRIGHT IN THIS DRAWING VESTS IN GEOTHETA, AND EXTENDS TO THE TAKING OF COPIES THEREOF IN WHOLE OR PART WITHOUT THE PRIOR CONSENT OF THE OWNER OF SUCH COPYRIGHT

GENERAL NOTES


- THESE NOTES SERVE AS AN ADDENDUM TO THE SPECIFICATION IN THE BILL OF QUANTITIES FOR THIS PROJECT. IN CASES WHERE THE SPECIFICATIONS IN THE BILL OF QUANTITIES DIFFER FROM THESE NOTES, THESE NOTES SHALL TAKE PREFERENCE.
- THE CONTRACTOR SHALL COMPLY WITH ALL STANDARDS/SPECIFICATIONS WHICH ARE REFERRED TO IN THESE NOTES.
- DRAWINGS SHALL BE CHECKED BY THE CONTRACTOR AND ANY DISCREPANCIES IN DIMENSIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER BEFORE WORK IS COMMENCED.
- DRAWINGS MAY NOT BE SCALED.

CONCRETE
EXCEPT WHERE MENTIONED OTHERWISE, THE CONCRETE WORK SHALL COMPLY WITH SANS 1200 G LATEST REVISION.


STRUCTURAL ELEMENT	CHARACTERISTIC 28 DAY STRENGTH (MPa)
--------------------	--------------------------------------

- FOUNDATIONS**
- BACKFILLING:** ALL BACKFILLING TO FOUNDATIONS TO BE COMPACTED TO 95% Mod. AASHTO DENSITY (min).
 - BLINDING:** ALL BASES TO BE PROVIDED WITH 75mm BLINDING.
 - ALL SPECIFIED FOUNDING LEVELS ARE PROVISIONAL AND NEED TO BE CONFIRMED BY THE ENGINEER ON SITE.


- NOTES**
- CULVERT TYPES**
1050ND CLASS 100D SPIGOT & SOCKET REINFORCED CONCRETE PIPES ON CLASS C BEDDING
 - CONSTRUCTION AND INSTALLATION CODES**
PER SANS 1200 OR PROJECT SPECIFICATION.
 - FOUNDATIONS**
A BEARING CAPACITY OF 200 kpa IS ASSUMED TO BE AVAILABLE.
 - FINISHING**
VISIBLE SURFACES - WOOD FLOAT (ie TOP OF SLAB FOR FOUNDATIONS).
 - REINFORCING**
FLOOR SLABS - MESH REF No 395
WING WALLS - MESH REF No 395 } ALL HIGH YIELD
 - JOINTS**
JOINTS BETWEEN PRECAST UNITS TO BE SEALED WITH GEOTEXTILE - 3.1mm THICK & 340g/m² OR SIMILAR.




SECTION D - D
1050ND CLASS 100D SPIGOT & SOCKET REINFORCED CONCRETE PIPE ON CLASS C BEDDING
SCALE 1:50




PLAN - TYPICAL ACCESS ROAD CULVERT FOR TRENCH
SCALE 1:75




PLAN - CULVERT HEADWALL
SCALE 1:25



SECTION A - A
SCALE 1:75



SECTION B - B
SCALE 1:75




SECTION C - C
SCALE 1:50

ISSUED FOR INFORMATION

REVISIONS		REFERENCE DRAWINGS		REFERENCE DRAWINGS		
REV	DATE	DESCRIPTION	DRG.No.	DRAWING TITLE	DRG.No.	DRAWING TITLE
A	2023-08-25	ISSUED FOR INFORMATION	502	PRE-DEPOSITION WORKS GENERAL ARRANGEMENT		
			503	FINAL HEIGHT GENERAL ARRANGEMENT		
			504	EARTHWORKS SECTIONS		

<p>GEOTHETA CONSULTING ENGINEERS AND SCIENTISTS</p> <p>Ground Floor, Twickenham Building, The Campus, Cnr Skane & Main, Bryanston, 2021 Republic of South Africa Phone : +27 11 575 3002 E-mail : hello@geotheta.com</p>				<p>DRAWN</p> <p>DATE</p> <p>CHECKED</p> <p>DATE</p> <p>DESIGNED</p> <p>DATE</p>	<p>SD</p> <p>2023-08-25</p> <p>S.M.</p> <p>2023-08-31</p> <p>S.M.I.H.</p> <p>2023-08-18</p>	<p>CLIENT</p> <p>HARMONY</p> <p>TITLE</p> <p>HARMONY - VALLEY TSF (CYCLONED)</p> <p>TYPICAL CULVERT DETAILS</p>
				<p>APPROVED BY</p> <p>NAME</p> <p>QUALIFICATION & REG. No.</p> <p>SIGNATURE</p> <p>DATE</p>	<p>CO-ORD SYSTEM</p> <p>SCALE</p>	<p>DRG No.</p> <p>2210513-512</p> <p>REV.</p> <p>A</p>

COPYRIGHT IN THIS DRAWING VESTS IN GEOTHETA, AND EXTENDS TO THE TAKING OF COPIES THEREOF IN WHOLE OR PART WITHOUT THE PRIOR CONSENT OF THE OWNER OF SUCH COPYRIGHT




REVISIONS		REFERENCE DRAWINGS		REFERENCE DRAWINGS		
REV	DATE	DESCRIPTION	DRG.No.	DRAWING TITLE	DRG.No.	DRAWING TITLE
A	2023-08-25	ISSUED FOR INFORMATION	502	PRE-DEPOSITION WORKS GENERAL ARRANGEMENT		
			514	TAILINGS DELIVERY PIPELINE DETAILS		


COPYRIGHT IN THIS DRAWING VESTS IN GEOTHETA, AND EXTENDS TO THE TAKING OF COPIES THEREOF IN WHOLE OR PART WITHOUT THE PRIOR CONSENT OF THE OWNER OF SUCH COPYRIGHT

GEOTHETA CONSULTING ENGINEERS AND SCIENTISTS Ground Floor, Twickenham Building, The Campus, Cnr Skene & Main, Bryanston, 2021 Republic of South Africa Phone : +27 11 575 3002 E-mail : hello@geotheta.com				DRAWN 2023-08-25 CHECKED S.M. DATE 2023-08-31 DESIGNED S.M./I.H. DATE 2023-08-18	CLIENT HARMONY TITLE HARMONY - VALLEY TSF (CYCLONED) TAILINGS DELIVERY PIPELINE LAYOUT
APPROVED BY NAME: IAN HAMMOND, QUALIFICATION & REG. No.: PR.ENG 20110169, SIGNATURE: [Signature], DATE: 2023-08				CO-ORD SYSTEM WGS 84 LO27 SCALE A1 1:5000 A3 1:10000	DRG No. 2210513-513 REV. A


ISSUED FOR INFORMATION




PLAN - TAILINGS DISTRIBUTION POINT FROM PLANT (1 No. REQUIRED)
SCALE 1:100



SECTION A
1:100



DETAIL '1' - ENLARGED PLAN ON TAILINGS DISTRIBUTION POINT FROM PLANT (1 No. REQUIRED)
SCALE 1:20




DETAIL '2' - PLAN ON TYPICAL TAILINGS DELIVERY STATION (75 No. REQUIRED)
SCALE 1:20

ISSUED FOR INFORMATION

REVISIONS		REFERENCE DRAWINGS		REFERENCE DRAWINGS		
REV	DATE	DESCRIPTION	DRG.No.	DRAWING TITLE	DRG.No.	DRAWING TITLE
A	2023-08-25	ISSUED FOR INFORMATION	513	TAILINGS DELIVERY PIPELINE LAYOUT	.	.

GEOTHETA CONSULTING ENGINEERS AND SCIENTISTS Ground Floor, Twickenham Building, The Campus, Cnr Skane & Main, Bryanston, 2021 Republic of South Africa Phone : +27 11 575 3002 E-mail : hello@geotheta.com				DRAWN DATE CHECKED DATE DESIGNED DATE	SD 2023-08-25 S.M. 2023-08-31 S.M.I.H. 2023-08-18	CLIENT HARMONY TITLE HARMONY - VALLEY TSF (CYCLONED) TAILINGS DELIVERY PIPELINE DETAILS
APPROVED BY NAME: IAN HAMMOND, QUALIFICATION & REG. No.: PR.ENG 20110169, SIGNATURE: [Signature], DATE: 2023-08				CO-ORD SYSTEM WGS 84 LO27	SCALE A1 AS SHOWN A3 AS SHOWN X2	DRG No. 2210513-514 REV. A


COPYRIGHT IN THIS DRAWING VESTS IN GEOTHETA, AND EXTENDS TO THE TAKING OF COPIES THEREOF IN WHOLE OR PART WITHOUT THE PRIOR CONSENT OF THE OWNER OF SUCH COPYRIGHT




PLAN - SILT TRAP
SCALE 1:150

NOTES:


1. WELD MESH TO BE REF 888 (Y12 @ 200) CENTRALLY PLACED.
2. MINIMUM REINFORCING LAP LENGTH TO BE 600mm.
3. EARTH ADJACENT TO CONCRETE TO BE COMPACTED.
4. ALL CONCRETE TO HAVE A SMOOTH FINISH.
5. ALL CONSTRUCTION JOINTS TO BE AS PER DETAIL '1'. PANEL SIZES TO BE APPROVED BY THE ENGINEER. JOINTS TO BE WELL CLEANED & SCRABBLED TO EXPOSE FRESH AGGREGATE & THOROUGHLY WETTED BEFORE NEXT POUR.
6. ALL HANDRAILS TO BE STANDARD M90 BALL TYPE TOP MOUNT HANDRAIL WITH STANCHIONS @ 2m c/c TYP. SECURED TO CONCRETE WITH M16 x 100mm LONG CINCH ANCHOR BOLTS C/W NUT & WASHER.
7. SILT TRAP INCLUDES INFRASTRUCTURE TO ENABLE CLEANING.




SECTION A - A
SCALE 1:75




DETAIL '1' - SECTION CONSTRUCTION JOINT
N.T.S.



SECTION D - D
SCALE 1:75



SECTION C - C
SCALE 1:75




SECTION B - B
SCALE 1:75

ISSUED FOR INFORMATION

REVISIONS		REFERENCE DRAWINGS		REFERENCE DRAWINGS		
REV	DATE	DESCRIPTION	DRG.No.	DRAWING TITLE	DRG.No.	DRAWING TITLE
A	2023-08-25	ISSUED FOR INFORMATION	502	PRE-DEPOSITION WORKS GENERAL ARRANGEMENT		
			511	SOLUTION OUTFALL TRENCH PLAN, SECTIONS & DTLS		
			602	SILT TRAP SPILLWAY DETAILS		
			603	RETURN WATER DAM GENERAL ARRANGEMENT		
			604	RETURN WATER DAM SECTIONS & DETAILS		


<p>GEOTHETA CONSULTING ENGINEERS AND SCIENTISTS</p> <p>Ground Floor, Twickenham Building, The Campus, Cnr Skane & Main, Bryanston, 2021 Republic of South Africa Phone : +27 11 575 3002 E-mail : hello@geotheta.com</p>				<p>DRAWN: 2023-08-25</p> <p>CHECKED: S.M.</p> <p>DATE: 2023-08-31</p> <p>DESIGNED: S.M./I.H.</p> <p>DATE: 2023-08-18</p>		<p>CLIENT: HARMONY</p> <p>TITLE: HARMONY - VALLEY TSF (CYCLONED) RETURN WATER DAM SILT TRAP PLAN, SECTIONS & DETAILS</p>	
<p>APPROVED BY:</p> <p>NAME: IAN HAMMOND, QUALIFICATION & REG. No.: PR.ENG 20110169, SIGNATURE: [Signature], DATE: 2023-08</p>				<p>CO-ORD SYSTEM: WGS 84 LO27</p> <p>SCALE: A1 AS SHOWN, A3 AS SHOWN X2</p>		<p>DRG No.: 2210513-601</p> <p>REV. A</p>	

COPYRIGHT IN THIS DRAWING VESTS IN GEOTHETA. AND EXTENDS TO THE TAKING OF COPIES THEREOF IN WHOLE OR PART WITHOUT THE PRIOR CONSENT OF THE OWNER OF SUCH COPYRIGHT




- NOTES:**
1. WELD MESH TO BE REF 617 CENTRALLY PLACED.
 2. MINIMUM REINFORCING LAP LENGTH TO BE 600mm.
 3. EARTH ADJACENT TO CONCRETE TO BE COMPACTED.
 4. ALL CONCRETE TO HAVE A SMOOTH FINISH.
 5. ALL CONCRETE CORNERS IN CONTACT WITH THE LINING TO BE CHAMFERED MIN. 25mm.
 6. ALL CONSTRUCTION JOINTS TO BE AS PER DETAIL '1'. PANEL SIZES TO BE APPROVED BY THE ENGINEER. JOINTS TO BE WELL CLEANED & SCRABBLED TO EXPOSE FRESH AGGREGATE & THOROUGHLY WETTED BEFORE NEXT POUR.


PLAN - SILT TRAP SPILLWAYS
SCALE 1:100




SECTION A - A
2 No. REQUIRED
SCALE 1:50



SECTION B - B
SILT TRAP SPILLWAY HDPE PORTION - 2 No. REQUIRED
SCALE 1:50



SECTION C - C
SILT TRAP SPILLWAY CONCRETE PORTION - 2 No. REQUIRED
SCALE 1:50




DETAIL '1' - SECTION CONSTRUCTION JOINT
N.T.S.

ISSUED FOR INFORMATION

REVISIONS		REFERENCE DRAWINGS		REFERENCE DRAWINGS		DRAWN		CLIENT	
REV	DATE	DESCRIPTION	DRG.No.	DRAWING TITLE	DRG.No.	DRAWING TITLE	DATE	DATE	CLIENT
A	2023-08-25	ISSUED FOR INFORMATION	502	PRE-DEPOSITION WORKS GENERAL ARRANGEMENT			2023-08-25		HARMONY
			601	SILT TRAP PLAN, SECTIONS & DETAILS					
			603	RETURN WATER DAM GENERAL ARRANGEMENT					
			604	RETURN WATER DAM SECTIONS & DETAILS					

GEOTHETA CONSULTING ENGINEERS AND SCIENTISTS Ground Floor, Twickenham Building, The Campus, Cnr Skane & Main, Bryanston, 2021 Republic of South Africa Phone : +27 11 575 3002 E-mail : hello@geotheta.com				DRAWN: 5D DATE: 2023-08-25 CHECKED: S.M. DATE: 2023-08-31 DESIGNED: S.M.I.H. DATE: 2023-08-18		TITLE: HARMONY - VALLEY TSF (CYCLONED) RETURN WATER DAM SILT TRAP PLAN, SECTIONS & DETAILS	
APPROVED BY: IAN HAMMOND NAME: IAN HAMMOND QUALIFICATION & REG. No.: PR.ENG 20110169 SIGNATURE: [Signature] DATE: 2023-08				CO-ORD SYSTEM: WGS 84 LO27 SCALE: A1 AS SHOWN, A3 AS SHOWN X2		DRG No.: 2210513-602 REV. A	


COPYRIGHT IN THIS DRAWING VESTS IN GEOTHETA, AND EXTENDS TO THE TAKING OF COPIES THEREOF IN WHOLE OR PART WITHOUT THE PRIOR CONSENT OF THE OWNER OF SUCH COPYRIGHT



TOPSOIL STOCKPILE

LEGEND:

- TOPOGRAPHICAL CONTOURS - DATED 2023-02-01 (0.5m INTERVALS)
- AREA TO BE LINED
- EXISTING ACCESS ROADS











ISSUED FOR INFORMATION

REVISIONS		REFERENCE DRAWINGS		REFERENCE DRAWINGS	
REV	DATE	DRG.No.	DRAWING TITLE	DRG.No.	DRAWING TITLE
A	2023-08-25	502	PRE-DEPOSITION WORKS GENERAL ARRANGEMENT		
		601	SILT TRAP PLAN, SECTIONS & DETAILS		
		602	SILT TRAP SPILLWAY DETAILS		
		604	RETURN WATER DAM SECTIONS & DETAILS		
		605	RETURN WATER DAM SPILLWAY DETAILS		
		606	RETURN WATER DAM UNDERDRAINAGE DETAILS		
		607	RETURN WATER DAM DECANT STRUCTURE DETAILS		

<p>GEOTHETA CONSULTING ENGINEERS AND SCIENTISTS</p> <p>Ground Floor, Twickenham Building, The Campus, Cnr Skane & Math, Bryanston, 2021 Republic of South Africa Phone : +27 11 575 3002 E-mail : hello@geotheta.com</p>				<p>APPROVED BY</p> <p>NAME: IAN HAMMOND QUALIFICATION & REG. No.: PRE.ENG 20110169 SIGNATURE: [Signature] DATE: 2023-08</p>	<p>DATE: 2023-08-25</p> <p>CHECKED: S.M.</p> <p>DATE: 2023-08-31</p> <p>DESIGNED: S.M.I.H.</p> <p>DATE: 2023-08-18</p>	<p>CLIENT: HARMONY</p> <p>TITLE: HARMONY - VALLEY TSF (CYCLONED) RETURN WATER DAM GENERAL ARRANGEMENT</p> <p>DRG No.: 2210513-603</p> <p>REV. A</p>
---	--	--	--	---	--	---

<p>CO-ORD SYSTEM: WGS 84 LO27</p>		<p>SCALE: A1 1:1000, A3 1:2000</p>	
-----------------------------------	--	------------------------------------	--

Copyright in this drawing vests in Geotheta, and extends to the taking of copies thereof in whole or part without the prior consent of the owner of such copyright.



ISSUED FOR INFORMATION


REVISIONS		REFERENCE DRAWINGS		REFERENCE DRAWINGS		
REV	DATE	DESCRIPTION	DRG.No.	DRAWING TITLE	DRG.No.	DRAWING TITLE
A	2023-08-25	ISSUED FOR INFORMATION	502	PRE-DEPOSITION WORKS GENERAL ARRANGEMENT		
			603	RETURN WATER DAM GENERAL ARRANGEMENT		
			606	RETURN WATER DAM UNDERDRAINAGE DETAILS		

APPROVED BY			
NAME	QUALIFICATION & REG. No.	SIGNATURE	DATE
IAN HAMMOND	PR.ENG 20110169		2023-08


DRAWN		DATE	
		2023-08-25	
CHECKED		S.M.	
DATE		2023-08-31	
DESIGNED		S.M.I.H.	
DATE		2023-08-18	
CO-ORD SYSTEM		SCALE	
A1	AS SHOWN		
A3	AS SHOWN X2		

CLIENT	
HARMONY	
TITLE	
HARMONY - VALLEY TSF (CYCLONED) RETURN WATER DAM SECTIONS & DETAILS	
DRG No.	REV.
2210513-604	A

COPYRIGHT IN THIS DRAWING VESTS IN GEOTHETA, AND EXTENDS TO THE TAKING OF COPIES THEREOF IN WHOLE OR PART WITHOUT THE PRIOR CONSENT OF THE OWNER OF SUCH COPYRIGHT




PLAN - RETURN WATER DAM SPILLWAY
SCALE 1:100




DETAIL '1' - SECTION CONSTRUCTION JOINT
N.T.S.


- NOTES:**
1. WELD MESH TO BE REF 617 CENTRALLY PLACED.
 2. MINIMUM REINFORCING LAP LENGTH TO BE 600mm.
 3. EARTH ADJACENT TO CONCRETE TO BE COMPACTED.
 4. ALL CONCRETE TO HAVE A SMOOTH FINISH.
 5. ALL CONCRETE CORNERS IN CONTACT WITH THE LINING TO BE CHAMFERED MIN. 25mm.
 6. ALL CONSTRUCTION JOINTS TO BE AS PER DETAIL '1'. PANEL SIZES TO BE APPROVED BY THE ENGINEER. JOINTS TO BE WELL CLEANED & SCRABBLED TO EXPOSE FRESH AGGREGATE & THOROUGHLY WETTED BEFORE NEXT POUR.




SECTION A - A
SCALE 1:50



SECTION B - B SPILLWAY HDPE PORTION
SCALE 1:50



SECTION C - C SPILLWAY CONCRETE PORTION
SCALE 1:50




SECTION D - D SPILLWAY CONCRETE PORTION
SCALE 1:50

ISSUED FOR INFORMATION

REVISIONS		REFERENCE DRAWINGS		REFERENCE DRAWINGS		GEOTHETA CONSULTING ENGINEERS AND SCIENTISTS				DRAWN		CLIENT		
REV	DATE	DESCRIPTION	DRG.No.	DRAWING TITLE	DRG.No.	DRAWING TITLE	Ground Floor, Twickenham Building, The Campus, Cnr Skane & Main, Bryanston, 2021 Republic of South Africa Phone : +27 11 575 3002 E-mail : hello@geotheta.com				DATE	SCALE	HARMONY	
A	2023-08-25	ISSUED FOR INFORMATION	502	PRE-DEPOSITION WORKS GENERAL ARRANGEMENT			APPROVED BY NAME: IAN HAMMOND, QUALIFICATION & REG. No.: PR.ENG 20110169, SIGNATURE: [Signature], DATE: 2023-08				2023-08-25	S.M.	HARMONY - VALLEY TSF (CYCLONED) RETURN WATER DAM SPILLWAY DETAILS	
			604	RETURN WATER DAM SECTIONS & DETAILS							2023-08-31	S.M./I.H.		
							CO-ORD SYSTEM: WGS 84 LO27, SCALE: A1 AS SHOWN, A3 AS SHOWN X2				DRG No. 2210513-605		REV. A	


COPYRIGHT IN THIS DRAWING VESTS IN GEOTHETA, AND EXTENDS TO THE TAKING OF COPIES THEREOF IN WHOLE OR PART WITHOUT THE PRIOR CONSENT OF THE OWNER OF SUCH COPYRIGHT



PLAN - RETURN WATER DAM UNDERDRAINAGE SYSTEM

SCALE 1:1500


RETURN WATER DAM



**SECTION B - B
DRAINAGE OUTLET PIPES TO MANHOLES**


SCALE 1:75

RETURN WATER DAM




DETAIL '1' - SECTION DRAINAGE MANHOLE

SCALE 1:25




**SECTION A - A
SLOTTED UNDERDRAINAGE SYSTEM IN BASIN**

SCALE 1:20



**SECTION C - C
NON-PERFORATED DRAINAGE OUTLET PIPES**

SCALE 1:20



**SECTION D - D
SLOTTED UNDERDRAINAGE SYSTEM IN BASIN**

SCALE 1:20

ISSUED FOR INFORMATION

REVISIONS		REFERENCE DRAWINGS		REFERENCE DRAWINGS		
REV	DATE	DESCRIPTION	DRG.No.	DRAWING TITLE	DRG.No.	DRAWING TITLE
A	2023-08-25	ISSUED FOR INFORMATION	502	PRE-DEPOSITION WORKS GENERAL ARRANGEMENT		
			603	RETURN WATER DAM GENERAL ARRANGEMENT		
			604	RETURN WATER DAM SECTIONS & DETAILS		


APPROVED BY			
NAME	QUALIFICATION & REG. No.	SIGNATURE	DATE
IAN HAMMOND	PR.ENG 20110169		2023-08

GEO THETA CONSULTING ENGINEERS AND SCIENTISTS	
Ground Floor, Twickenham Building, The Campus, Cnr Steane & Main, Bryanston, 2021 Republic of South Africa Phone : +27 11 575 3002 E-mail : hello@geotheta.com	


DATE	SCALE
2023-08-25	A1 AS SHOWN
2023-08-31	A3 AS SHOWN X2

CLIENT	TITLE	DRG No.	REV.
HARMONY	HARMONY - VALLEY TSF (CYCLONED) RETURN WATER DAM UNDERDRAINAGE DETAILS	2210513-606	A


COPYRIGHT IN THIS DRAWING VESTS IN GEOTHETA, AND EXTENDS TO THE TAKING OF COPIES THEREOF IN WHOLE OR PART WITHOUT THE PRIOR CONSENT OF THE OWNER OF SUCH COPYRIGHT




PLAN - RETURN WATER DAM DECANT STRUCTURE
SCALE 1:150




DETAIL '1' - SECTION - DECANT OUTLET PIPE ANCHOR BLOCK
SCALE 1:25




SECTION B - B PUDDLE FLANGES
SCALE 1:50




DETAIL '2' - TYPICAL SECTION LINER ATTACHMENT TO CONCRETE
SCALE 1:10



PLAN - DECANT OUTLET PIPE ANCHOR BLOCK
SCALE 1:50



SECTION C - C DECANT OUTLET PIPES
SCALE 1:50



SECTION A - A DECANT OUTLET PIPES TO PUMP CHAMBER
SCALE 1:75

- NOTES:**
1. MINIMUM COVER TO REINFORCING TO BE 50mm.
 2. MINIMUM REINFORCING LAP LENGTH TO BE 600mm.
 3. EARTH ADJACENT TO CONCRETE TO BE COMPACTED.
 4. ALL CONCRETE TO HAVE A SMOOTH FINISH.
 5. ALL CONCRETE CORNERS IN CONTACT WITH THE LINING TO BE CHAMFERED MIN. 25mm.

REVISIONS		REFERENCE DRAWINGS		REFERENCE DRAWINGS		DRAWN		CLIENT						
REV	DATE	DESCRIPTION	DRG.No.	DRAWING TITLE	DRG.No.	DRAWING TITLE	DATE	SCALE	CLIENT					
A	2023-08-25	ISSUED FOR INFORMATION	502	PRE-DEPOSITION WORKS GENERAL ARRANGEMENT			2023-08-25	S.M.	HARMONY					
			603	RETURN WATER DAM GENERAL ARRANGEMENT			2023-08-31	S.M.I.H.	HARMONY - VALLEY TSF (CYCLONED)					
			604	RETURN WATER DAM SECTIONS & DETAILS			2023-08-18	SCALE	RETURN WATER DAM DECANT STRUCTURE DETAILS					
<p>GEOTHETA CONSULTING ENGINEERS AND SCIENTISTS</p> <p>Ground Floor, Twickenham Building, The Campus, Cnr Steane & Main, Bryanston, 2021 Republic of South Africa Phone : +27 11 575 3002 E-mail : hello@geotheta.com</p>							<p>APPROVED BY</p> <p>NAME: IAN HAMMOND, QUALIFICATION & REG. No.: PR.ENG 20110169, SIGNATURE: [Signature], DATE: 2023-08</p>		<p>SCALE</p> <p>SCALE: AS SHOWN X2</p>		<p>DRG No.</p> <p>2210513-607</p>		<p>REV.</p> <p>A</p>	
<p>Copyright in this drawing vests in Geotheta, and extends to the taking of copies thereof in whole or part without the prior consent of the owner of such copyright</p>							<p>CO-ORD SYSTEM</p> <p>WGS 84 LO27</p>		<p>ISSUED FOR INFORMATION</p>					



DESIGN DETAIL DRAFTING CC

P O Box 1432, Noordheuwel. 1756
 Tel : 084 581 4179
 Email : niel@3ddd.co.za / sonja@3ddd.co.za

DRAWING REGISTER

Client/Company: HARMONY

Project name: HARMONY VALLEY TAILINGS STORAGE FACILITY


Project no: 2210513

Revision: A

Date: 2023/08/25

Drawing number	Description	Revision	Date
HARMONY VALLEY TSF (CYCLONED)			
2210513-501	OVERALL SITE LAYOUT	A	Aug-23
2210513-502	PRE-DEPOSITION WORKS GENERAL ARRANGEMENT	A	Aug-23
2210513-503	FINAL HEIGHT GENERAL ARRANGEMENT	A	Aug-23
2210513-504	EARTHWORKS SECTIONS	A	Aug-23
2210513-505	EARTHWORKS SECTIONS & DETAILS	A	Aug-23
2210513-506	DRAINAGE SECTIONS & DETAILS	A	Aug-23
2210513-507	DRAINAGE COLLECTOR PIPES SECTIONS & DETAILS	A	Aug-23
2210513-508	SOLUTION TRENCH SECTIONS & DETAILS	A	Aug-23
2210513-509	PENSTOCK INTAKE SECTIONS & DETAILS	A	Aug-23
2210513-510	PENSTOCK CATWALK TYPICAL DETAILS	A	Aug-23
2210513-511	SOLUTION OUTFALL TRENCH PLAN, SECTIONS & DETAILS	A	Aug-23
2210513-512	TYPICAL CULVERT DETAILS	A	Aug-23
2210513-513	TAILINGS DELIVERY PIPELINE LAYOUT	A	Aug-23
2210513-514	TAILINGS DELIVERY PIPELINE DETAILS	A	Aug-23
RETURN WATER DAM			
2210513-601	SILT TRAP PLAN, SECTIONS & DETAILS	A	Aug-23
2210513-602	SILT TRAP SPILLWAY DETAILS	A	Aug-23
2210513-603	RETURN WATER DAM GENERAL ARRANGEMENT	A	Aug-23
2210513-604	RETURN WATER DAM SECTIONS & DETAILS	A	Aug-23
2210513-605	RETURN WATER DAM SPILLWAY DETAILS	A	Aug-23
2210513-606	RETURN WATER DAM UNDERDRAINAGE DETAILS	A	Aug-23
2210513-607	RETURN WATER DAM DECANT STRUCTURE DETAILS	A	Aug-23

ID	Task Mode	Task Name	Duration	Start	Finish	Predecessors	2025 Qtr 2			2025 Qtr 3			2025 Qtr 4			2026 Qtr 1			2026 Qtr 2		
							Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	
1		Valley TSF Construction Schedule	276 days	Mon 25/04/28	Mon 26/05/18																
2		Contract Start date	1 day	Mon 25/04/28	Mon 25/04/28																
3		Safety file approval	5 days	Mon 25/04/28	Fri 25/05/02	2SS															
4		Onboarding Process, Medical, Training & Inductions	12 days	Mon 25/04/28	Tue 25/05/13	2SS															
5		Site Establishment	14 days	Wed 25/05/14	Mon 25/06/02																
6		Laydown area	8 days	Wed 25/05/14	Fri 25/05/23	4															
7		Offices	10 days	Tue 25/05/20	Mon 25/06/02	6SS+4 days															
8		Plant establishment	4 days	Wed 25/05/14	Mon 25/05/19	4															
9		Initial setting out	1 day	Wed 25/05/14	Wed 25/05/14	4															
10		South east wall section	128 days	Tue 25/06/03	Thu 25/11/27																
11		Site Clearance	13 days	Tue 25/06/03	Thu 25/06/19	5															
15		TSF bulk earthworks	59 days	Fri 25/06/20	Wed 25/09/10																
28		Drains	69 days	Thu 25/08/14	Tue 25/11/18																
33		Solution trench	51 days	Thu 25/08/07	Thu 25/10/16																
37		Liner installation	66 days	Thu 25/08/28	Thu 25/11/27																
38		Surface preparation	30 days	Thu 25/08/28	Wed 25/10/08	30SS+10 days															
39		Panel placement	60 days	Mon 25/09/01	Fri 25/11/21	38SS+2 days															
40		Seam welding	60 days	Wed 25/09/03	Tue 25/11/25	39SS+2 days															
41		Non-destructive testing	60 days	Fri 25/09/05	Thu 25/11/27	40SS+2 days															
42		North West wall section	149 days	Thu 25/08/07	Tue 26/03/03																
73		Basin section	151 days	Mon 25/10/20	Mon 26/05/18																
74		Penstock	106 days	Tue 25/10/21	Tue 26/03/17																
78		Catwalk	42 days	Wed 25/12/03	Thu 26/01/29																
81		Site Clearance	50 days	Mon 25/10/20	Fri 25/12/26																
84		TSF bulk earthworks	40 days	Mon 25/12/01	Fri 26/01/23																
85		Preparation of approved in-situ material	20 days	Mon 25/12/01	Fri 25/12/26																
86		TSF basin and wall area	20 days	Mon 25/12/01	Fri 25/12/26	83SS+20 days															
87		Supply and place tailings material over liner	30 days	Mon 25/12/15	Fri 26/01/23																
88		TSF basin and wall area	30 days	Mon 25/12/15	Fri 26/01/23	86SS+10 days															
89		Drains	58 days	Tue 26/02/17	Thu 26/05/07																
92		Liner installation	81 days	Mon 26/01/26	Mon 26/05/18																
93		Surface preparation	35 days	Mon 26/01/26	Fri 26/03/13	88															
94		Panel placement	75 days	Wed 26/01/28	Tue 26/05/12	93SS+2 days															
95		Seam welding	75 days	Fri 26/01/30	Thu 26/05/14	94SS+2 days															
96		Non-destructive testing	75 days	Tue 26/02/03	Mon 26/05/18	95SS+2 days															
97		Return Water Dam	243 days	Thu 25/05/15	Mon 26/04/20																



ID	Task Mode	Task Name	Duration	Start	Finish	Predecessors	2025 Qtr 2		2025 Qtr 3			2025 Qtr 4			2026 Qtr 1			2026 Qtr 2	
							Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr
98		Site clearance	75 days	Thu 25/05/15	Wed 25/08/27														
99		Drain existing RWD	60 days	Thu 25/05/15	Wed 25/08/06	9													
100		Clear and grub	10 days	Thu 25/08/07	Wed 25/08/20	99													
101		Topsoil stripping and stockpiling	10 days	Thu 25/08/14	Wed 25/08/27	100SS+5 days													
102		RWD bulk earthworks	135 days	Thu 25/08/21	Wed 26/02/25														
103		Excavation	66 days	Thu 25/08/21	Thu 25/11/20														
104		RWD basin	25 days	Thu 25/08/21	Wed 25/09/24	25;100													
105		RWD embankment key-cut	10 days	Thu 25/09/18	Wed 25/10/01	104SS+20 days													
106		Silt trap	2 days	Thu 25/10/02	Fri 25/10/03	105													
107		Spillway	1 day	Thu 25/11/20	Thu 25/11/20	113SS+15 days													
108		Preparation of approved in-situ material	120 days	Thu 25/09/11	Wed 26/02/25														
109		RWD basin	120 days	Thu 25/09/11	Wed 26/02/25	104SS+15 days													
110		RWD embankment	10 days	Thu 25/10/09	Wed 25/10/22	105SS+15 days													
111		Silt trap	2 days	Fri 25/11/21	Mon 25/11/24	107													
112		Construct embankment walls	65 days	Thu 25/09/11	Wed 25/12/10														
113		RWD embankments	30 days	Thu 25/10/30	Wed 25/12/10	110SS+15 days													
114		Stormwater diversion bund wall	10 days	Thu 25/09/11	Wed 25/09/24	104SS+15 days													
115		Underdrainage	50 days	Thu 25/09/25	Wed 25/12/03														
116		Excavate trench	30 days	Thu 25/09/25	Wed 25/11/05	109SS+10 days													
117		Place drainage material	30 days	Thu 25/10/16	Wed 25/11/26	116SS+15 days													
118		Cover with bidim and backfill	20 days	Thu 25/11/06	Wed 25/12/03	117SS+15 days													
119		Concrete works	105 days	Tue 25/11/25	Mon 26/04/20														
120		Geocells	45 days	Thu 26/01/15	Wed 26/03/18	128SS+20 days													
121		Spillway	20 days	Thu 26/02/12	Wed 26/03/11	120SS+20 days;11													
122		Silt trap	30 days	Tue 25/11/25	Mon 26/01/05	111													
123		Concrete curing time	28 days	Thu 26/03/12	Mon 26/04/20	120SS+1 day;121;													
124		RWD Liner	60 days	Thu 25/11/27	Wed 26/02/18														
125		Surface preparation	20 days	Thu 25/11/27	Wed 25/12/24	118SS+15 days													
126		Panel placement	45 days	Thu 25/12/04	Wed 26/02/04	125SS+5 days													
127		Seam welding	45 days	Thu 25/12/11	Wed 26/02/11	126SS+5 days													
128		Non-destructive testing	45 days	Thu 25/12/18	Wed 26/02/18	127SS+5 days													
129		Tailings delivery pipeline	90 days	Tue 25/10/21	Mon 26/02/23														
130		Final delivery pipeline	90 days	Tue 25/10/21	Mon 26/02/23	53													
131		De-establishment	44 days	Tue 25/12/30	Fri 26/02/27	130SS+50 days													
132		Completion	0 days	Mon 26/05/18	Mon 26/05/18	131;5;10;42;73;9'													

